



Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Project Division

Name of Work: Providing Children Play Equipments and Senior Citizen Gym Equipments and Landscape Development to Parks in Ward no. 08, Byatarayanapura of Yelahanka Zone

Modified Estimate

Sl. No.	Description of item	Rate	Unit	Nos	Est. Cost. In Rs.			10946851.00		
					Dimension			Total Qty	Rate in Rs	Amount in Rs
A	Civil Works				L in m	B in m	D in m			
1	KSRRB M200-10.1. Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness complete as per specifications. I. By Manual Means: A. In area of light jungle. MORTH Specification No. 201. (BCSR 2016-2017, Page 136, Item No 18.13)									
			Ha							
	C Sector park									
	For open gym platform			1	9.65	6.20		59.83		
				1	8.50	4.15		35.28		
	Total Quantity									
	Total Scheduled-B Quantity								0.10	
	Quantity upto 125%								0.18	
								0.10	58594.95	5572.67
2	Excavation in Soil with Dozer KSRRB M300-11. Excavation for road way in all types of soil by mechanical means including cutting and pushing the earth to site of embankment including trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections complete as per specifications. MORTH Specification No. 301. (BCSR 2016-2017, Page 143, Item No 19.11)									
			Cum							
	C Sector park									
	For open gym platform			1	9.65	6.20	0.25	14.96		
				1	8.50	4.15	0.25	8.82		
	Cqal layout park									
	Children Play Equipment			1	30.00	8.00	0.50	120.00		
	Inside the			1	21.00	8.00	0.50	84.00		
	surrounding Supporting Wall			1	22.00	8.00	0.50	88.00		
				1	144.00	0.55	0.80	63.36		
	surrounding Darin Disilting			1	205.00	0.50	0.95	97.38		
	For Flgging			1	211.00	0.60	0.60	75.96		
				1	211.00	0.45	0.60	56.97		
	Cqal layout park			1	211.00	0.30	0.40	25.32		
	Walking Track			1	151.50	2.10	0.40	127.26		
				1	8.00	3.00	0.40	9.60		
	Disilting of Surrounding Drain			1	187.00	0.60	0.60	67.32		
				1	194.80	0.60	0.60	70.13		
	Total Quantity								909.07	
	Total Scheduled-B Quantity								1178.04	
	Quantity upto 125%								909.07	210.28
										191159.08

3	KSRRB M300-Construction of Embankment with Material Gravel/Murum KSRRB M300-53. Construction of embankment with approved material Gravel /Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (BCSR 2016-2017, Page 148, Item No 19.60)									
			Cum							
	C Sector park									
	For open gym platform		1	9.65	6.20	0.45	26.92			
			1	8.50	4.15	0.45	15.87			
	For Children Play Area		1	20.00	9.00	0.45	81.00			
			1	8.50	4.15	0.45	15.87			
	Cqal layout park									
	Walking Track		1	151.50	2.10	0.30	95.45			
			1	8.00	3.00	0.30	7.20			
	Total Quantity							242.32		
	Total Scheduled-B Quantity							945.00		
	Quantity upto 125%							242.32	362.04	87728.08
4	KSRRB M400- Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory									
			Cum							
	For Chairs plotform		5	2.10	1.90	0.30	5.99			
	For Gajeeba plotform		2	34.00		0.30	20.40			
	Total Quantity							26.39		
	Total Scheduled-B Quantity							109.00		
	Quantity upto 125%							26.39	1999.60	52759.45
5	KSRRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2									
			Cum							
	C Sector park									
	For open gym platform		1	9.65	6.20	0.15	9.15			
			1	8.50	4.15	0.15	5.33			
	Cqal layout park									
	surrounding Suporting Wall		1	155.00	0.55	0.15	12.79			
			1	205.00	0.50	0.15	15.68			
	CQAl park									
	Bed Concrete for Surrounding Drain		2	204.00	0.45	0.15	27.54			
	Bed Con For Chairs plotform		5	2.10	1.90	0.15	2.99			
	Bed Con For Gajeeba plotform		2	34.00		0.15	10.20			
	Total Quantity							83.69		
	Total Scheduled-B Quantity							110.62		
	Quantity upto 125%							83.69	5834.56	488274.15

KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS.(BCSR 2016-2017, Page 101, Item No 14.6)

Sqm

Qty Carried from Item no. EIRL-8

Cqal layout park
For Walking Track

1

151.50

2.10

318.15

Total Quantity

Total Scheduled-B Quantity

318.15

Quantity upto 125%

225.40

Quantity above 125%

281.75

1093.31

308040.09

KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1 : 6 stone hammerd dressed in courses not less than 20 ems high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13
(BCSR 2016-2017, Page 23, Item No 5.5)

36.40

1093.31

39796.48

CQAl park

Cum

Surrounding Drain

1

204.00

0.45

0.60

55.08

Damaged Wall

1

34.40

0.45

0.60

9.29

Total Quantity

Total Scheduled-B Quantity

64.37

Quantity upto 125%

99.84

64.37

5019.38

323087.45

KSRB 4-1 .6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement@ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggretes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.(BCSR 2016-2017, Page 12, Item No 4.6)

Cum

Chairs plotform fixing

5

1.90

2.20

0.150

3.14

Cqal layout park

surrounding

1

155.00

0.55

0.700

59.68

1

205.00

0.50

0.650

66.63

Coping concrete Surrounding Drain

1

204.00

0.40

0.150

12.24

Coping concrete Surrounding Drain

1

204.00

0.45

0.150

13.77

Packing conc for surrounding drain

1

75.00

0.35

0.150

3.94

Sahakaranagar park

For Pole Fixation

15

0.30

0.30

0.300

0.41

Total Quantity

Total Scheduled-B Quantity

159.79

Quantity upto 125%

61.40

Quantity above 125%

76.75

6522.67

500614.92

83.04

6522.67

541626.21

Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, including cutting, gridding the edge to half/full round wherever required, labour, curing complete as per specification (BCSR 2016-2017, Page 109, Item No 14.62)

	Sqm					
Open gym equipment fixing	1	15.00	6.50		97.50	
For Gajeeba platform	2	34.00			68.00	
For Chairs platform	5	2.10	1.90		19.95	

Total Quantity
Total Scheduled-B Quantity
Quantity upto 125%

185.45
330.00
185.45 **1300.70** **241214.82**

10 KSRRB M2200-8.1. Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification complete as per specifications. A. Granular material MORTH Specification No. 2204 (BCSR 2016-2017, Page 225, Item No 28.11)

Total Quantity
Total Scheduled-B Quantity
Quantity upto 125%

0.00
27.60
0.00 **628.17** **0.00**

11 Providing chain link fencing 50mm size of 8 gauge properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (BCSR 2016-2017, Page 262, Item No 37.3)

	Sqm					
Rise Fencing - Childrens park	1	415.00	1.20	498.00		
Damaged fence	1	59.00	1.40	82.60		
Sahakarinagar park						
For Damaged fence	1	36.00	1.20	43.20		
	1	55.00	1.80	99.00		
	1	40.00	1.40	56.00		
	1	15.00	1.40	21.00		
	1	47.00	1.80	84.60		
	1	27.00	1.80	48.60		

Total Quantity
Total Scheduled-B Quantity
Quantity upto 125%

933.00
747.00
933.00 **790.01** **737079.33**

	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1 :2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 ems. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop												
				mtrs									
	Rise Fencing - Childrens park				208	1.50				311.25			
	Damaged fence				30	1.50				44.25			
	Sahakarinagar park												
	For Pole Fixation				7	2.70				18.90			
					3	3.20				9.60			
					5	2.40				12.00			
	Total Quantity									396.00			
	Total Scheduled-B Quantity									457.80			
	Quantity upto 125%									396.00			
										981.82		388800.72	
13	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint (BCSR 2016-2017, Page 262, Item No 37.4)												
				M									
	Rise Fencing - Childrens park				1	415.00				415.00			
	Damaged fence				2	59.00				118.00			
	Sahakarinagar park												
	For Pole Fixation				2	36.00				72.00			
					2	55.00				110.00			
					2	40.00				80.00			
					2	15.00				30.00			
					2	47.00				94.00			
					2	27.00				54.00			
	Total Quantity									973.00			
	Total Scheduled-B Quantity									976.00			
	Quantity upto 125%									973.00			
										388.41		377922.93	
14	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in												
				Sqm									
	Gate, Tatanagar &				2	3.00	1.90			11.40			
	Total Quantity									11.40			
	Total Scheduled-B Quantity									16.80			
	Quantity upto 125%									11.40			
										13847.28		157858.99	

15	Fabricating, providing and erecting in poiston of M S Ornamental security Grill without hot dip using 75 x 12mm M S Flat for alround frame work with verticals at the centre and horizontal centere support M S Square of 20 x20 mm of different heights as shown in the drawing are to be fixed at 16 cms C/C for suqare bars of full height and at 8cms C / C for bottom rods providg ornamental C I Designers at thebotom and C I arrows inthe midle and top. The entire frame work is to be fixed by means of expansion bolts to the brick pillars with necesary drillling holes. the work includes providng two coats of enamel painting over one coatr of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulleycranes etc as per specification and drawings. (BCSR 2016-2017, Page 41, Item No 7.33)									
				Kgs						
	Total Quantity							0.00		
	Total Scheduled-B Quantity							7271.42		
	Quantity upto 125%							0.00	157.04	0.00
16	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (BCSR 2016-2017, Page 25, Item No 5.26.1)									
				Sqm						
	Open gym equipment									
				1	9.65		0.20	1.93		
				1	8.30		0.20	1.66		
	CQAI Layout									
	Surrounding Drain			1	204.00		0.40	81.60		
	Total Quantity							85.19		
	Total Scheduled-B Quantity							3.60		
	Quantity upto 125%							4.50	1123.28	5054.76
	Quantity above 125%							80.69	1123.28	90637.46
17	KSRB15-3.7 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (BCSR 2016-2017, Page 113, Item No 15.15)									
				sqm						
	Cqal layout park									
	surrounding			1	144.00		0.550	79.20		
	Total Quantity							79.20		
	Total Scheduled-B Quantity							7.20		
	Quantity upto 125%							9.00	292.51	2632.59
	Quantity above 125%							70.20	292.51	20534.20

Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete
(BCSR 2016-2017, Page 25, Item No 5.30)

	Nos						
Surrounding Open gym equipment	1	57.00				57.00	
Surrounding Children equipment	1	10.00				10.00	
For Surrounding Drain	1	174.00				174.00	
For Path way	2	147.00				294.00	
		No. of Kerbs= /0.45				1189	
Total Quantity						1188.00	
Total Scheduled-B Quantity						596.00	
Quantity upto 125%						745.00	375.22
Quantity above 125%						443.00	375.22
							279538.90
							166222.46

19 KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8.
(BCSR 2016-2017, Page 182, Item No 24.2)

	Sqm						
Open gym equipment	1	57.00		0.35	19.95		
For Walking Track	2	151.00		0.35	105.70		
For Inside Park Surrounding	1	354.00		0.35	123.90		
Total Quantity					249.55		
Total Scheduled-B Quantity					101.00		
Quantity upto 125%					126.25	71.93	9081.16
Quantity above 125%					123.30	71.93	8868.97

20 Providing and applying Enamel Metal Painting two coats (excluding priming coat) over new steel or other metal surfaces brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, with materials, labour complete as per specifications.
(BCSR 2016-2017, Page 182, Item No 24.1)

	Sqm						
For Chain link fencing in CQAL	2	415.00		1.5	1245.00		
For Chain link fencing in Sahakaranagar	2	385.00		2.4	1848.00		
Total Quantity					3093.00		
Total Scheduled-B Quantity					684.00		
Quantity upto 125%					855.00	98.30	84046.50
Quantity above 125%					2238.00	98.30	219995.40

Supply and Fixing of Pull Down Challenger. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All weld d joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at II the welding points prior to finishing . All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for th e handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified internat ional certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS ma rk as has been issued in the EN16630 safety certificates. Size_ L x W x H): 2570 x 805 x 2685 mm. Weight: 85.4 Kg Safety Area : 6287 x 4858 mm Capacity_2 Persons.

21

Unit

1

Total Quantity

1.00

Total Scheduled-B Quantity

1.00

Quantity upto 125%

1.00

1.00

266400.00

266400.00

Supply and fixing of Seated Chest Press. Metal: All tubular steel of 2.5mm thickness are galvanized and z inc dipped. Joints are Robotic welded. All welded joints t1H • scalloped as necessary and welded to an approved MIG process. All welds an • 111 csed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w 11ltling points prior to finishing. All metal parts are powder coated using AKZO Nobel (11 ca t Wall powder to the thickness of 80-120 microns. All metal parts are tested in rn 1r a lt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handle!,,Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely Prt' ,ssembled equipment modules. Maintenance: Maintain according to EN 166630 and the maintenance guide. Safety: All products must be tested and certified to mt•(•1EN16630 safety standards with GS test mark. The EN 16630,certificates must be issued by a reputed notified international certifying agency such as IPEMA, 1UV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS inark as has

22

Total Rate in Rs

255300.00

Unit

Unit

1

Total Quantity

1.00

Total Scheduled-B Quantity

1.00

Quantity upto 125%

1.00

1.00

255300.00

255300.00

23	Supply and fixing of Self Weighted Rower. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards only by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS. The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must carry a GS mark on it. Size_L x W x H: 1390 x 805 x 1100 mm. Weight: 42.4 Kg Safety Area: 3790 x 3205 mm Capacity_1 Person.			
			Unit	
			1	
	Total Quantity			1.00
	Total Scheduled-B Quantity			1.00
	Quantity upto 125%			1.00
				183150.00
				183150.00
24	Supply and fixing of Elliptical Cross Trainer. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality Grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with the tender document. All products must clearly display the GS mark as has been used in the EN16630 safety certificates. Size_L x W x H: 126/582 x 1764 mm. Weight : 43.5 Kg Safety Area: 4322 x 3632 mm Capacity 1 Person.			
			Unit	
			1	
	Total Quantity			1.00
	Total Scheduled-B Quantity			1.00
	Quantity upto 125%			1.00
				155400.00
				155400.00

25	Supply and Fixing of Rider. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO 7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. 5 Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark-EN16630 Certificate must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN 16630 safety certificate. Size L x W x H: 910 x 655 x 1270 mm. Weight: 29.5 Kg Safety Area: 3310 x 1100 mm Capacity_1 Person									
			Unit							
				1					1.00	
			Total Quantity						1.00	
			Total Scheduled-B Quantity						1.00	
			Quantity upto 125%						1.00	99900.00
26	Supply and Fixing of Bicycle. Metal: All tubular steel of 25mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel Great Wall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO 7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. each 1 125000 125000 131188 131188 134500 134500 Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards only by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS. The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. Size L x W x H: 1000 x 498 x 120 mm. Weight: 51.5 Kg Safety Area: 3400 x 3498 mm Capacity_ 1 Persons.									
			Unit							
				1					1.00	
			Total Quantity						1.00	
			Total Scheduled-B Quantity						1.00	
			Quantity upto 125%						1.00	138750.00

27	Supply and Fixing of Arm & Pedal Bike. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings : Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety : All products must be tested and certified to meet EN16630 safety standards only by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. Size_ L x W x H: 830 x 500 x 1450 mm. Weight: 32 Kg Safety Area: 3830 x 2900 mm Capacity_ 1 Persons.			
		Unit		
			1	
	Total Quantity			1.00
	Total Scheduled-B Quantity			1.00
	Quantity upto 125%			1.00
				1.00
				188700.00
				188700.00
28	Supply and Fixing of Tai Chi Spinners . Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel Great Wall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance -free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with the tender document . All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size_ L x W x H: 1120 x 1150 x 1620 mm. Weight: 39 Kg Safety Area: 3520 x 3550 mm Capacity_ 3 Persons.			
		Unit		
			1	
	Total Quantity			1.00
	Total Scheduled-B Quantity			1.00
	Quantity upto 125%			1.00
				1.00
				127650.00
				127650.00

29	Supply and fixing of Twist Stepper. Metal: All tubular steel of 2.Smrn thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-GreatWall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark.The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV ,CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630			
	Unit	1	1.00	
	Total Quantity		1.00	
	Total Scheduled-B Quantity		1.00	
	Quantity upto 125%		1.00	199800.00
30	Supply and fixing of Big Shoulder Wheel. Metal: All tubular steel of 2.Smni thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joint ure scalloped as necessary and welded to an approved MIG process. All welds arc' dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w elding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles.CV-10 Bearings: Maintenance-free ball bearings. Scope of delivery:1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to rmeet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size_L x W x H): 845 x 810 x 1710 mm. Weight: 34 Kg Safety Area: 3224 x 3376 mm Capacity_2 Persons.			
	Unit	1	1.00	
	Total Quantity		1.00	
	Total Scheduled-B Quantity		1.00	
	Quantity upto 125%		1.00	133200.00
31	Supply and fixing of HD Health Walker. Metal: All tubular steel of 2.Smm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joint s are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a S% NaCl solution			
	Unit	1	1.00	
	Total Quantity		1.00	
	Total Scheduled-B Quantity		1.00	
	Quantity upto 125%		1.00	155400.00
32	Supply. and Fixing of HD Sit Up Station. Metal: All tubular steel of 2.Smm thick111".5 are galvanized and z inc dipped.Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is appied at a ll the weldint1 points prior to fini shing. All metal parts are powder coated using AKZO Nobel-Grca t Wall powder to the thickness of 80-120 microns.			
	Unit	1	1.00	

		Total Quantity				1.00		
		Total Scheduled-B Quantity				1.00		
		Quantity upto 125%				1.00	138750.00	138750.00
33	Supply and fixing of HD Squat Pushing. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles 13 Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size (L x W x H): 2270 x 635 x 1640 mm. Weight: 60.2Kg. Safety Area: 5300 * 3685mm. Capacity 2 Persons							
		Unit						
			1				1.00	
		Total Quantity				1.00		
		Total Scheduled-B Quantity				1.00		
		Quantity upto 125%				1.00	238650.00	238650.00
34	Supply and fixing of HD Waist Twister. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles 13 Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size (L x W x H): 2270 x 635 x 1640 mm. Weight: 60.2Kg. Safety Area: 5300 * 3685mm. Capacity 2 Persons							
		Unit						
			1				1.00	
		Total Quantity				1.00		
		Total Scheduled-B Quantity				1.00		
		Quantity upto 125%				1.00	144300.00	144300.00
35	Supply and Fixing of HD Mini Ski. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles 13 Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size (L x W x H): 2270 x 635 x 1640 mm. Weight: 60.2Kg. Safety Area: 5300 * 3685mm. Capacity 2 Persons							
		Unit						
			1				1.00	
		Total Quantity				1.00		
		Total Scheduled-B Quantity				1.00		
		Quantity upto 125%				1.00	177600.00	177600.00
36	Supply and fixing of HD Double Health Walker. Metal: All tubular steel of 2.50mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles 13 Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size (L x W x H): 2270 x 635 x 1640 mm. Weight: 60.2Kg. Safety Area: 5300 * 3685mm. Capacity 2 Persons							
	Total Rate in Rs	266400.00	Unit					
			Unit					
			1				1.00	
		Total Quantity				1.00		
		Total Scheduled-B Quantity				1.00		
		Quantity upto 125%				1.00	266400.00	266400.00

37	Providing and fixing granite benches as per design, specification and fixing as per the directions of the engineer in charge.							
		Unit						
			22			22.00		
	Total Quantity					22.00		
	Total Scheduled-B Quantity					10.00		
	Quantity upto 125%					12.00	11710.50	140526.00
	Quantity above 125%					10.00	11710.50	117105.00
38	MANUFACTURING:-PROVIDING AND FIXING A GAZEBO os Size 22 feet dia approximate) made of MS Round pipe of 6 inches diameter of 12 SWG for pillars 10feet in height,in which 8ft will be above the ground level and 2 feet embedded in cement concrete and provided with MS plate on top of the pillars.MS I section 100x50mm of heavy gauge for Rafters)is placed between the poles on top of the flush plate.Also MS rectangular tubes of 100x40mm are to be mounted vertically on all 8pillars.MS rectangular tubes of 40x20mm reepers are welded horizontally in between the rectangle tubes for a distance of 1 feet approximately so as to get the desired octangol Shape for fixing approved qualoity Corrugated Managlore tiles on the roof 2 layers as per the design. Flat design tiles and rigid tiles are to be provided on Existing reepers and pointed with cement mortar.The Gazebo is to be fixed ob asuitable platform the central height being 15 to 16 feet and including allround bed Concrete 1:4:8 and tampered with fine red earth with cement slurry.the works includes earthwork excavation concreteing,masonry work and cost of all materials,labour equipments, machinery with all load and lift loading							
		Unit						
			2			2.00		
	Total Quantity					2.00		
	Total Scheduled-B Quantity					2.00		
	Quantity upto 125%					2.00	430596.75	861193.50
B	Borewell							
39	Sinking Borewell of 165mm dia clear, using fast rig in all strata including over-burden upto 20mts. Fixing of casing Pipes, collars and cap with necessary cutting and threading including, transportation of Rig and supporting vehicle, crew charge and cost of consumbles, etc, complete including yield testing at the final depth with a minimum woring of compressor for one hour. (excluding cost of casing pipes, collars and cap, etc.) a) 0.00 to50.00 Mtr-							
		Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	339.66	0.00
40	b) 50.00 to 100.00 Mtr	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	444.00	0.00
41	c) 100.00 to 150.00 Mtr	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	493.95	0.00
42	d) 150.00 to 200.00 Mtr	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	521.70	0.00
43	e) 200.00 to 250.00 Mtr	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	603.84	0.00
44	f) 250.00 to 300.00 Mtr	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	647.13	0.00
45	g) 300.00 to 350.00 Mtr	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	690.42	0.00

46	Supply of ISI Mark 175mm nominal Bore, Plain end steel casing Pipe-grade of steel Fee 4100 of wakk thickness 504mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel electric or basic oxygen process in fandum length of 5 to 7mtr. Both ends threaded confirming to Is554/1985 one end fixed with socket confirming to IS 270:2001 and other end with screwed pipes. All pipes shall be reasonably free from defectes. The tubes shall be resonably straigth should be with ISI Marking Weighting 25.10 kg/mtr (Inclusive of all taxes and durties) Prices include Collar - medium duty. Page No.ii, LNo.53 PRE Bang SR 2016-17							
		Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	1470.75	0.00
47	a) Above 20mtrs and upto 30mtrs.@15%	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	50.95	0.00
48	b) Above 30mtrs@30%	Rmtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	101.90	0.00
49	175mm M.S. B-Class Casing Collar (P.No.ii,LNo.55)	Nos						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	166.50	0.00
50	175mm dia Casing Cap (P.No.ii,LNo.54)	Nos						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	111.00	0.00
51	Supply and delivery at site brand new submesible PUMPSET suitable for bore well of 150 mm dia and having declared duty conditions as detailed below and satisfying performances characteristics for pump and motor as declared by bureau of Indian standards. The pump should confirm to IS:8034-1970 (with all its latest amendments) and should bear the ISI mark 12.5 HP 20 stage (CRI Pumps)(SR 2016-17 page xxxl sl no 23)							
	H=150m dish 150 LPM	Set						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	78366.00	0.00
52	Supply and Delivery of Galvanized Mild steel Heavy Class (C-Class) conforming to IS 1239-1979 PART-I/1979 with lastest amendments with ISI mark (one end fitted with ISI mark heavy duty collar and other end fitted with Protective cover) 50 mm dia							
	50mm dia G.I Pipe with heavy duty	Mtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	416.25	0.00
53	Submersible Cable: Supply and Delivery of brand new best make PVC insulated cable of flat 3core (sheathed) of nominal cross sectional area containing to IS 894-1997 with latest amendments (as per SPD) 4 Square mm							
	280*2+10	Mtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	89.91	0.00
54	50 mm dia GI Collar Heavy	Mtr						
	Total Quantity					0.00		
	Total Scheduled-B Quantity					100.00		
	Quantity upto 125%					0.00	144.30	0.00


55	Meter and Panel Board: Supply and Delivery of Meter and Panel Board: Meter Board unit one number of MS Box of size 300x120 mm size fabricated out of 2mm thick sheet metal with sealable door arrangement for munting the CTS (if any) cutouts 3phase dia 4 wire energy meter and cable box complete. A transparent glass piece should be provided where the energy meter reading could be read. Panel Board: One number of cubicle type of control panel board to operate on 50c/400/400v Upto 10 to 20 HP								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	12210.00	0.00
56	50mm dia G.I.N.R. Valve								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	950.16	0.00
57	Erection & Commissioning of work of pumpset including aligning and balancing with all necessary erection of materials and labour including supply and erection of two pair of supporting clamps, one borewell cap, cable clips and water tight gland cable protectors, bolts nuts valves and gauges etc, all job including fixing sluice valve, non return valve etc, and connecting delivery side of pumpset to rising main etc, complete.								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	943.50	0.00
58	Power Capacitor: Supply and Delivery of brand new best make capacitor conforming to IS:2834-1986 with latest amendments with ISI mark of required capacity tested and approved by KPTCL authorities and erection, electrification and commissioning of the same at the location of the respective pumpsets. Supply & Delivery of best indigenous brand new MCB (Miniature Circuit Breaker) of required capacity as per IS:8828-1978 and its latest amendment with ISI mark 6/10/20/25/40 amps with sealable box with MCB 3 KVAR								
			Mtr						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	510.60	0.00
59	Supplyin mmdia 2mm 2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive pase etc., and running before cocreting the slab. The conduit should be tiled to the reinforcement rods by using binding wires and unused ways of junction boxes and plpe ends should be covered using PVC end enclosuers. Run with 18SWGFI fish wire wherever necessary (P-2,1-1)								
	b)25mm dia 2mm thick		Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	49.15	0.00
60	Supplying of TPST with rewirable porcelain channels in SM enclosure. (P-30. 1-1)								
	b)32amps		Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	1630.37	0.00


61	Supplying and fixing polished wood board made of not less than 15 mm thick plan on both sides with planks made out of more than two pieces and fixing the same to the wall using wooden plugs, screws etc.,(p-30 1-2)	20X20X2.5	Nos								
	Total Quantity										
	Total Scheduled-B Quantity										
	Quantity upto 125%										
							0.00				
							100.00				
							0.00	341.66			0.00
62	Supplying and wiring adopting loop system in existing PVC Conduit/casing capping using Copper PVC insulated multistrand 2x1.5 Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box. The other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet (P-3. 1-8)										
	(a) Short Point upto 3Mtr form tapping point to outlet via switch		Rmtr								
	Total Quantity										
	Total Scheduled-B Quantity						0.00				
	Quantity upto 125%						100.00				
							0.00	209.79			0.00
63	© Long Point above 6 Mtr. Upto 10 Mtr. From tapping point to out let via switch		Rmtr								
	Total Quantity						0.00				
	Total Scheduled-B Quantity						100.00				
	Quantity upto 125%						0.00	441.16			0.00
64	Supplying 6 A flush/projected type socket and a 6Amps flush/projected type SP switch either surface/flush mounting in a existing gang box or a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as										
	(b)6Amps3/5 Way		Nos								
	Total Quantity						0.00				
	Total Scheduled-B Quantity						100.00				
	Quantity upto 125%						0.00	127.07			0.00
65	Wiring for lighting /power circuit using one of PVC insulated 1100V grade multis and Copper conductor single core cable in open or consealed system of wiring (P-9, 1-20)										
	Group "B"© 2.5Sq.mm		Rmtr								
	Total Quantity						0.00				
	Total Scheduled-B Quantity						100.00				
	Quantity upto 125%						0.00	25.14			0.00
66	Supplying and fixing PBBC backelite straight or slant batten holder &wiring 60w/230 Volts lamps (P-13, 1-2)										
	Group B		Rmtr								
	Total Quantity						0.00				
	Total Scheduled-B Quantity						100.00				
	Quantity upto 125%						0.00	67.13			0.00
67	Supplying and fixing of LED type panel borad indicating lamp with required colour suitable for 220 v A.C. 50 Hz 12/24v D.C (P-38, 1-35)										
			Nos								
	Total Quantity						0.00				
	Total Scheduled-B Quantity						100.00				
	Quantity upto 125%						0.00	515.48			0.00
68	Labour charges for laying of 1.1KV class UG cable when supplied departmentally/ agency in existing trench GI pipe/stoneware pipe/on wall/on pole as required (P-68, 1-11)										
	a)10Sqmm to 16Sqmm		Rmtr								
	Total Quantity						0.00				
	Total Scheduled-B Quantity						100.00				
	Quantity upto 125%						0.00	179.82			0.00

69	Digging of trench of 0.6mtrs deepx0.5 mtrs wide refilling the required gorund level and consolidating etc., complete (P-68, 1-12)								
	a)in soil(ordinary)		Rmtr						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	9.59	0.00
70	Supplying and fixing of class 'A' GI pipe on pole /wall/drain crossing with necessary clamping arrangement for UG cable of 1.1KV class(P-69, 1-15)								
	a)65mm(upto 150Sqmm)		Rmtr						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	47.95	0.00
71	Supplying and fixing of heay duty cable glands suitable for UG cable of 1.1KV class metal only (P-69, 1-17)								
	a)25mm dia		Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	287.71	0.00
72	Supplying and fixing miniature circuit breakers on existing MCB disitribution boards using necessary fixing materials and wiring complete as required (P-34, 1-13)								
	5-32 amps TPN		Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	79.12	0.00
73	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete (P-30, 1-3) a) 32Amps								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	1204.79	0.00
74	Supplying and fixing L.T. cast Iorn pot heads suitable for 1.1. KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,(P-69, 1-16) a)								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	119.88	0.00
75	Supplying, fixing, wiring, earth electrode for gounding conduits, I.C cotouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit... The pit should be filled with equal propotion of salt and charcoal 150mm alround the pipe to complete depth. The connection from the to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and checkunts etc., the pipe shall have 16 through holes of 122mm dia (P-66, 1-7)								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	311.47	0.00
76	Supplying decorative horizontal type street light fluorescent fitting weather and water proof complete with low loss open construction copper wound ferromagnetic ballast,starter,locking type brass contact holders with 1 No. of 4 feet 40 watts fluorescent tube completely wired for use on 230/250 volts. 50cycles AC supply with opal reeded Perspex cover at bottom complete fitting (P-17, 1-6)								
			Nos						
	Total Quantity						0.00		
	Total Scheduled-B Quantity						100.00		
	Quantity upto 125%						0.00	2338.33	0.00

[illegible]


EIRL-2	0334 Sand/ Artificial Sand/ Manufactured Sand									
			Cum.							
	below Children Play Equipement			1	11.50	10	0.30	34.50		
	Total Quantity							34.50	1887.00	65101.50
EIRL-3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2									
			Sqm							
	Cqal layout park surrounding			1	144.00		0.700	100.80		
	Total Quantity							100.80	351.25	35406.00
EIRL-4	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)									
			Sqm							
	Total Rate in Rs		91.11	Sqm						
			Sqm							
	Cqal layout park Drain Slabs			1	204.00	(0.6+0.6+0.6)=1.8		367.20		
	Total Quantity							367.20	91.11	33455.59
EIRL-5	Providing precast slab of 100mm thick including cost of all aterials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer									
			Sqm							
	Cqal layout park surrounding Darin			1	204.00	0.900		183.60		
	Total Quantity							183.60	2337.00	429073.20
	Total Construction Cost									10946851.00


Asst. Engineer
Yelahanka Project Division
BBMP Bangalore


Asst. Exe. Engineer
Yelahanka Project Division
BBMP Bangalore
Yelahanka Zone
BBMP, Bangalore - 92


Executive Engineer
Yelahanka Project Division
BBMP Bangalore
Yelahanka Zone
BBMP, Bangalore-92

Technical Sanction
Accorded For Rs. 10946851.00
Head of A/C P.32.13
CER NO : 57A Dt: 28/12/2020


CE (YNK)